Bruhath Benglauru Mahangara Palike, Dasarhalli Zone
Office of the Executive Engineer, Dasarhalli Division.
Schedule - B

Name of the Work : Improvements to drains & construction of culvert at Bhoomika layout (near Gangamma house) in Bagalagunte in ward no. 14

Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted Naveen J	
				In Figures (Rs)	In Words (Rs)
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	Cum	138	88.01	Rupees Eighty Eighty and One Paisa Only
2	Providing and constructing granite / trap / basalt rubble stone masonry in foundation with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specification	Cum	140.76	5908.24	Rupees Five Thosand One Hundred and Eight and Twenty Four Paisa Only
3	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	276	105.18	Rupees One Hundred and Five and Eighteen Paisa Only
4	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC Cement @220 kgs with 20 mm and down size graded granite metal course aggregates @ 0.84 cum and fine aggregates @0.56 cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well comated, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per , Specification	Cum	18.4	5517.8	Rupees Five Thosand Five Hundred and Seventeen and Eighty Paisa Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted Naveen J	
				In Figures (Rs)	In Words (Rs)
5	Supplying and fixing precast rainforced concee slab 25 cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Sqm	285.2	4992.64	Rupees Four Thosand Nine Hundred and Ninety Two and Sixty Four Paisa Only
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 15 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	138	79.22	Rupees Seventy Nine and Twenty Two Paisa Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division